



BICSI

Exam Questions DCDC-003.1

BICSI Data Center Design Consultant (DCDC)

NEW QUESTION 1

What is the low temperature that must be maintained in a data center according to NEB standards?

- A. 55 degrees
- B. 60 degrees
- C. 65 degrees
- D. 70 degrees
- E. 75 degrees

Answer: C

NEW QUESTION 2

What is the minimum distance recommended between a data center's backup generator and the main data center building?

- A. 10 feet
- B. 20 feet
- C. 30 feet
- D. 40 feet

Answer: C

NEW QUESTION 3

what is the ANSI/TIA-942 recommended operational temperature

- A. 60F to 75F
- B. 68F to 77F
- C. 80F to 90F
- D. -10??C to +45??C

Answer: B

NEW QUESTION 4

What are the 3 types of Authentication for access control?

- A. Type 4 - What you possess
- B. Type 5 - What you desire
- C. Type 6 - What you create
- D. Type 1 - What you have Type 2 - What you know Type 3 - What you are

Answer: D

NEW QUESTION 5

What kind of height clearance should data center access roads have?

- A. A Minimum clear road width and sixteen (16) ft height clearance throughout.
- B. A Minimum clear road width and six(06) ft height clearance throughout.
- C. A Minimum clear road width with fourteen (14)ft hight clearance throughout.
- D. None Of The Above.

Answer: C

NEW QUESTION 6

What is the recommended floor loading capacity for a data center?

- A. 1000 lbs per s
- B. ft.
- C. 1250 lbs per s
- D. ft.
- E. 1500 lbs per s
- F. ft.
- G. 1750 lbs per s
- H. ft.
- I. 2000 lbs per s
- J. ft.

Answer: C

NEW QUESTION 7

According to NEB, what is the recommended rate of temperature change per hour in a data center?

- A. 36 degrees
- B. 45 degrees
- C. 54 degrees
- D. 63 degrees
- E. 72 degrees

Answer: C

NEW QUESTION 8

What is the clearance required between the cold aisle and the CRAC unit?

- A. 2 feet
- B. 4 feet
- C. 6 feet
- D. 8 feet

Answer: D

NEW QUESTION 9

How do you calculate thermal load in a data center?

- A. IT Thermal Output + Cooling System
- B. IT Thermal Output + Lighting System
- C. IT Thermal Output + PDU System
- D. IT Thermal Output + Cooling System + Lighting System
- E. IT Thermal Output + Cooling System + Lighting System + PDU System

Answer: E

NEW QUESTION 10

What is the minimum required headroom for overhead cable tray?

- A. 3"
- B. 6"
- C. 9"
- D. 12"

Answer: B

NEW QUESTION 10

What is the difference between a raised floor and a solid floor?

- A. Raised floor allows for better airflow and cable management
- B. Solid floor allows for better cooling efficiency and higher load capacity
- C. Raised floor is cheaper and easier to install
- D. Solid floor is more flexible and adaptable to changing needs

Answer: A

NEW QUESTION 15

What is the recommended clearance space required for hot and cold aisles in a data center?

- A. 1-2 feet
- B. 3-4 feet
- C. 5-6 feet
- D. 7-8 feet

Answer: B

NEW QUESTION 16

what is the ASHRAE maximum relative humidity recommended.

- A. 45%
- B. 50%
- C. 55%
- D. 60%

Answer: D

NEW QUESTION 20

What is the appropriate fire rating requirements for a command center?

- A. 1/2 hour
- B. 1 hour
- C. 2 hours
- D. 3 hours

Answer: B

NEW QUESTION 23

What is the recommended amount of fuel supply to be available to a class F4 data center?

- A. 24 hours
- B. 48 hours
- C. 72 hours
- D. 96 hours

Answer: D

NEW QUESTION 24

what is minimum recommended space for secured storage area?

- A. 100 square feet B 240 square feet
- B. 250 square feet
- C. 280 square feet
- D. None of above

Answer: C

NEW QUESTION 27

Why do larger data centers require more H DAs?

- A. to ensure maximum horizontal cable lengths are not exceeded and to avoid cable congestion
- B. to reduce energy consumption and carbon footprint
- C. to increase server processing speed by minimizing latency
- D. to provide redundancy and failover mechanisms

Answer: A

NEW QUESTION 30

What is the NEBS GR-3028-CORE recommended operational temperature.

- A. -25??F to +125??F (-32??C to +52??C)
- B. -30??F to +110??F (-34??C to +43??C)
- C. -20??F/-28?? C minimum and up to a maximum of 104 ?? Fahrenheit/40?? Celsius
- D. Up To 140 Degrees Fahrenheit /60 Degrees Celsius

Answer: C

NEW QUESTION 34

what is the most common energy storage solution and what are the two types

- A. Lithium-ion battery, sealed and unsealed
- B. Flywheel, vertical and horizontal
- C. Supercapacitor, cylindrical and prismatic
- D. Lead-acid battery, vented and valve regulated Nickel-cadmium battery, vented and valve regulated

Answer: D

NEW QUESTION 36

What is the clearance required between AC units?

- A. Mi
- B. of 2 ft but recommended 6 ft.
- C. Mi
- D. of 4 ft but recommended 6 ft.
- E. Mi
- F. of 6 ft but recommended 8 ft.
- G. Mi
- H. of 8 ft but recommended 10 ft.

Answer: B

NEW QUESTION 41

where should the telecommunications room for the operations center be located

- A. inside the computer room
- B. within a designated telecommunication space outside of computer rooms
- C. on another floor entirely from the operations center
- D. in an offsite location

Answer: B

NEW QUESTION 46

What is the preferred location of the power distribution unit?

- A. a service gallery outside the computer room, if the A H J and feeder distances allow
- B. under each server rack
- C. in an unused area of another floor
- D. inside a ventilation duct

Answer: A

NEW QUESTION 50

where should printers be located

- A. beside high traffic areas
- B. near equipment that has active air flow to cool them down
- C. in a dedicated print room with dedicated air handling system
- D. placed outdoor, away from building facilities

Answer: C

NEW QUESTION 54

What is the recommendation regarding row length?

- A. Do not exceed 20 racks in length and dead-end rows not to exceed ten racks long
- B. Maximum twenty-five racks in each row only
- C. Ten Racks in Length
- D. None
- E. All

Answer: A

NEW QUESTION 57

What is the recommended amount of fuel supply needing to be available to a class F2 data center?

- A. 12 hours
- B. 18 hours
- C. 24 hours
- D. 30 hours
- E. 36 hours

Answer: C

NEW QUESTION 58

How do you calculate the thermal load of the lighting system inside a data center?

- A. Rated power * .01
- B. IT load * .01
- C. Rated power * .02
- D. IT load * .02
- E. Rated power * .05

Answer: C

NEW QUESTION 60

why does the entrance room designer need to meet with each anticipated access provider?

- A. To determine their electrical, space, interface, and other facility requirements
- B. As an alternative approach to save cost
- C. To know about hardware requirement only
- D. none of above

Answer: A

NEW QUESTION 62

What are main concepts in choosing location of the entrance room?

- A. If possible, it should be very close, and, in the computer room distance limitations for T1,T3,E1,and E3 circuits,
- B. Should not be near to Data Center
- C. Dedicated location outside building
- D. All of these

Answer: A

NEW QUESTION 64

According to TIA-942, what is the low temperature that must be maintained in a data center?

- A. 60 degrees
- B. 65 degrees

- C. 68 degrees
- D. 70 degrees
- E. 75 degrees

Answer: C

NEW QUESTION 67

What is the maximum recommended number of racks in an aisle?

- A. 20 racks
- B. 10 racks
- C. 30 racks
- D. 40 racks

Answer: A

NEW QUESTION 69

What is the formula for reliability?

- A. $R = e^T$
- B. $R = e^{-T}$
- C. $R = T/e$
- D. $R = \log(T)$

Answer: B

NEW QUESTION 72

Apart from marine cargo ports, hazardous material transport roadways, transportation roadways, and flight paths, what other things should a data centre be at least one mile away from?

- A. Waste-disposal units and dumpsites only.
- B. Petroleum storage installations like petrol stations & oil storage facilities only.
- C. Fireworks manufacturing companies only.
- D. All of The Above

Answer: D

NEW QUESTION 75

What types of electrical equipment is typically located inside the computer room

- A. power distribution units, not power distribution equipment, remote power panels, and power strips
- B. transformers only
- C. Uninterrupted Power Supply (UPS) only
- D. Circuit Breakers only

Answer: A

NEW QUESTION 80

What is the recommended height of a ceiling in a data center or telecommunications room?

- A. 012 ft
- B. 1015ft(correct)
- C. 1112ft
- D. 1120151

Answer: B

NEW QUESTION 84

what are the dead loads of a structure?

- A. Static loads due to force of gravity on fixed building elements (correct)
- B. Dynamic loads due to external forces like suction winds and rain
- C. Loads due to snow, wash
- D. Temperature fluctuations leading to expansion and contraction

Answer: A

NEW QUESTION 88

.....

Thank You for Trying Our Product

We offer two products:

1st - We have Practice Tests Software with Actual Exam Questions

2nd - Questions and Answers in PDF Format

DCDC-003.1 Practice Exam Features:

- * DCDC-003.1 Questions and Answers Updated Frequently
- * DCDC-003.1 Practice Questions Verified by Expert Senior Certified Staff
- * DCDC-003.1 Most Realistic Questions that Guarantee you a Pass on Your FirstTry
- * DCDC-003.1 Practice Test Questions in Multiple Choice Formats and Updatesfor 1 Year

100% Actual & Verified — Instant Download, Please Click
[Order The DCDC-003.1 Practice Test Here](#)